

SIEMENS LOW VOLTAGE UN-ASSEMBLED MOBILE HOME LOAD CENTER PANEL. BOX FACTORY INSTALLED MAIN BREAKER 30 (1 INCH) SPACES INTERIOR ALLOWING 60 MAX CIRCUITS. 1-PHASE 3-WIRE SYSTEM RATED 120/240V (200A). SPECIAL FEATURES: FACTORY INSTALLED GROUND BAR.



last modified:

03/12/2018