



SIEMENS LOW VOLTAGE ASSEMBLED MOBILE HOME LOAD CENTER PANEL. LOAD CENTER MAIN LUG 24 (1 INCH) SPACES INTERIOR ALLOWING 48 MAX CIRCUITS. 1-PHASE 3-WIRE SYSTEM RATED 120/240V (200A). SPECIAL FEATURES: FACTORY INSTALLED GROUND BAR, GRAY TRIM.

---

last modified:

10/21/2022 

