



SIEMENS LOW VOLTAGE ASSEMBLED MOBILE HOME LOAD CENTER PANEL. LOAD CENTER FACTORY INSTALLED MAIN BREAKER 16 (1 INCH) SPACES INTERIOR ALLOWING 32 MAX CIRCUITS. 1-PHASE 3-WIRE SYSTEM RATED 120/240V (150A). SPECIAL FEATURES: FACTORY INSTALLED GROUND BAR, GRAY TRIM.

last modified:

10/21/2022 

